

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

Table 1. Summary of Results

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	Description		
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
DRINKING	GTMO-1681-ADMIN-HALL-WFBA-FD* (BLDG 1681-1)	Administrative Building (AD) - Fountains outside Admin Office	2.3	NO	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBA-FD-2 (BLDG 1681-1)	Administrative Building (AD) - Fountains outside Admin Office	3	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBB-FD* (BLDG 1681-2)	Administrative Building (AD) - Fountains outside Admin Office	3.4	NO	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBB-FD-2 (BLDG 1681-2)	Administrative Building (AD) - Fountains outside Admin Office	3.9	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBC-FD* (BLDG 1681-3)	Administrative Building (AD) - Fountains outside Admin Office	170	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBC-FD-2 (BLDG 1681-3)	Administrative Building (AD) - Fountains outside Admin Office	3.2	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBD-FD* (BLDG 1681-4)	Administrative Building (AD) - Fountains outside Admin Office	4.6	NO	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-ADMIN-HALL-WFBD-FD-2 (BLDG 1681-4)	Administrative Building (AD) - Fountains outside Admin Office	2.3	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-CAFETERIA-WFBA-FD* (BLDG 1681-10)	School Cafeteria (P-1) - Common Eating Area	120	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-CAFETERIA-WFBA-FD-2 (BLDG 1681-10)	School Cafeteria (P-1) - Common Eating Area	83	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-CAFETERIA-WFBB-FD* (BLDG 1681-11)	School Cafeteria (P-1) - Common Eating Area	320	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-CAFETERIA-WFBB-FD-2 (BLDG 1681-11)	School Cafeteria (P-1) - Common Eating Area	140	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A1-RM-WFCOMB-FD (BLDG 1681-26)	A-Wing - Storage for Music Room	110	YES	N/A	N/A	28	5.9	Taken Out of Service	N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)		Recommended Level = 20ppb	
Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)							Description	First Draw (ppb) (See note 2)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
DRINKING	GTMO-1681-A3-RM- WFCOMB-FD (BLDG 1681-28)	A-Wing - Music Room	1700	YES	N/A	N/A	120	21	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A5-RM- WFCOMB-FD (BLDG 1681-30)	A-Wing - IT Room	960	YES	N/A	N/A	64	33	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A7-RM- WFCOMB-FD (BLDG 1681-32)	A-Wing - PTO Room	130	YES	N/A	N/A	72	4.8	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A9-RM- WFCOMB-FD (BLDG 1681-34)	A-Wing - Girl Scouts Room	1100	YES	N/A	N/A	200	3.1	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A11-RM- WFCOMB-FD (BLDG 1681-36)	A-Wing - Boy Scouts Room	720	YES	N/A	N/A	44	5.4	Taken Out of Service	N/A	N/A
DRINKING	GTMO-AWING-WFC-FD* (BLDG 1681-37)	A-Wing - Cooler Fountain located at end of A Wing	45	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-AWING-WFC-FD-2 (BLDG 1681-37)	Cooler Fountain located at end of A Wing	330	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A12-RM- WFCOMB-FD (BLDG 1681-40)	A-Wing - Storage Room	1000	YES	N/A	N/A	9	190	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A10-RM- WFCOMB-FD (BLDG 1681-42)	A-Wing - Supply Storage	82	YES	N/A	N/A	38	2.6	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A8-RM- WFCOMB-FD (BLDG 1681-44)	A-Wing - Supply Storage	66	YES	N/A	N/A	160	18	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A6-RM- WFCOMB-FD (BLDG 1681-46)	A-Wing - Supply Storage	170	YES	N/A	N/A	31	4.5	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-A2-RM- WFCOMB-FD (BLDG 1681-48)	A-Wing - Science Storage	86	YES	N/A	N/A	41	7.5	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B18-BATH-GIRLS- HHWF-FD (BLDG 1681-54)	B-Wing - Girls' Bathroom in B- Wing	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
DRINKING	GTMO-1681-B19-BATH-BOYS-HHWF-FD (BLDG 1681-60)	B-Wing - Boys' Bathroom in B-Wing	3.6	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-B1-RM-WFCOMB-FD (BLDG 1681-63)	B-Wing - Computer Room	110	YES	N/A	N/A	500	17	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B3-RM-WFCOMB-FD (BLDG 1681-65)	B-Wing - Printer Room	160	YES	N/A	N/A	23	non-detect	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B2-LOUNGE-WFCOMB-FD (BLDG 1681-67)	B-Wing - Teachers' Lounge	74	YES	N/A	N/A	810	30	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B4A-RM-WFCOMB-FD (BLDG 1681-69)	B-Wing - School Psychologist	11	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-B4B-RM-WFCOMB-FD (BLDG 1681-71)	B-Wing - Speech Therapy	4.1	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-B6-RM-WFCOMB-FD (BLDG 1681-73)	B-Wing - Foreign Language	7.7	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-B8-RM-WFCOMB-FD (BLDG 1681-75)	B-Wing - Gifted Students	46	YES	N/A	N/A	1.6	70	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B10-RM-WFCOMB-FD (BLDG 1681-77)	B-Wing - Unlabeled Room	1500	YES	N/A	N/A	12	2.9	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-B12-RM-WFCOMB-FD (BLDG 1681-79)	B-Wing - Book Storage	180	YES	N/A	N/A	130	6.9	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B14-RM-WFCOMB-FD (BLDG 1681-82)	Rooms B14 and B16 combined into one bigger room - Art Room	300	YES	N/A	N/A	38	14	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-B16-RM-WFCOMB-FD (BLDG 1681-85)	Rooms B14 and B16 combined into one bigger room - Art Room	93	YES	N/A	N/A	1300	120	Taken Out of Service	N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
DRINKING	GTMO-1681-BWING-WFB-FD (BLDG 1681-86)	Bubbler Fountain located at end of B Wing	36	YES	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-C2-RM-WFCOMB-FD (BLDG 1681-89)	C-Wing - 2nd Grade Room	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-C4-RM-WFCOMB-FD (BLDG 1681-93)	C-Wing - 4th Grade Room	180	YES	N/A	N/A	8.5	1.7	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C6-RM-WFCOMB-FD (BLDG 1681-97)	Rooms C6 and C8 combined into one bigger room - 3rd Grade Room	470	YES	N/A	N/A	7.7	3.1	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C8-RM-WFCOMB-FD (BLDG 1681-100)	Rooms C6 and C8 combined into one bigger room - 3rd Grade Room	1900	YES	N/A	N/A	4.2	non-detect	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C10-RM-WFCOMB-FD (BLDG 1681-103)	Rooms C10 and C12 combined into one bigger room - Kindergarten Room	250	YES	N/A	N/A	12	21	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-C12-RM-WFCOMB-FD (BLDG 1681-106)	Rooms C10 and C12 combined into one bigger room - Kindergarten Room	140	YES	N/A	N/A	59	17	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-C14-RM-WFCOMB-FD (BLDG 1681-109)	Rooms C14 and C16 combined into one bigger room - Pre-K (Sure Start) Room	15	NO	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GTMO-1681-C16-RM-WFCOMB-FD (BLDG 1681-112)	Rooms C14 and C16 combined into one bigger room - Pre-K (Sure Start) Room	400	YES	N/A	N/A	130	5.1	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-CWING-WFB-FD* (BLDG 1681-114)	Bubbler Fountain - Cooler Fountain located at end of C Wing	130	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-CWING-WFB-FD-2 (BLDG 1681-114)	Bubbler Fountain - Cooler Fountain located at end of C Wing	130	YES	N/A	N/A	N/A	N/A	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-C15-RM-WFCOMB-FD (BLDG 1681-116)	Rooms C15 and C17 combined into one bigger room - PSCD Room	130	YES	N/A	N/A	20	13	Routine Control Measures Only	N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
DRINKING	GTMO-1681-C17-RM-WFCOMB-FD (BLDG 1681-119)	Rooms C15 and C17 combined into one bigger room - PSCD Room	510	YES	N/A	N/A	1900	89	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-C13-RM-WFCOMB-FD (BLDG 1681-122)	Rooms C11 and C13 combined into one bigger room - 4th Grade Room	120	YES	N/A	N/A	15	5.2	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C11-RM-WFCOMB-FD (BLDG 1681-125)	Rooms C11 and C13 combined into one bigger room - 4th Grade Room	140	YES	N/A	N/A	10	4.7	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C9-RM-WFCOMB-FD (BLDG 1681-128)	Rooms C9 and C7 combined into one bigger room - 1st Grade	74	YES	N/A	N/A	20	non-detect	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C7-RM-WFCOMB-FD (BLDG 1681-131)	Rooms C9 and C7 combined into one bigger room - 1st Grade	930	YES	N/A	N/A	3.8	1.4	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C5-RM-WFCOMB-FD (BLDG 1681-134)	C-Wing - Unlabeled Room	120	YES	N/A	N/A	5.7	non-detect	Routine Control Measures Only	N/A	N/A
DRINKING	GTMO-1681-C3-RM-WFCOMB-FD (BLDG 1681-138)	C-Wing - ET Room	130	YES	N/A	N/A	30	non-detect	Taken Out of Service	N/A	N/A
DRINKING	GTMO-1681-C1-RM-WFCOMB-FD (BLDG 1681-140)	C-Wing - Supply Room	470	YES	N/A	N/A	50	2.7	Taken Out of Service	N/A	N/A
COOKING	GTMO-1681-CAFETERIA-K-KA-FD (BLDG 1681-12)	Pair of sinks situated back to back with another pair of sinks - Cafeteria Kitchen	4.4	NO	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GTMO-1681-CAFETERIA-K-KB-FD (BLDG 1681-13)	Pair of sinks situated back to back with another pair of sinks - Cafeteria Kitchen	5.6	NO	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GTMO-1681-CAFETERIA-K-HHW-FD (BLDG 1681-14)	School Cafeteria (P-1) - Cafeteria Kitchen	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GTMO-1681-CAFETERIA-K-KC-FD (BLDG 1681-15)	School Cafeteria (P-1) - Cafeteria Kitchen	2.1	NO	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GTMO-1681-CAFETERIA-K-KD-FD (BLDG 1681-16)	Pair of sinks situated back to back with another pair of sinks - Cafeteria Kitchen	6.9	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)		Recommended Level = 20ppb	
Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)							Description	First Draw (ppb) (See note 2)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-ADMIN-BATH-WOMENS-HHWA-FD (BLDG 1681-5)	Administrative Building (AD) - Womens' Restroom in Admin Office	14	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-ADMIN-BATH-WOMENS-HHWA-FD (BLDG 1681-6)	Administrative Building (AD) - Womens' Restroom in Admin Office	3.4	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-ADMIN-BATH-MENS-HHW-FD (BLDG 1681-7)	Administrative Building (AD) - Mens' Restroom in Admin Office	7.3	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-ADMIN-LOUNGE-LHW-FD (BLDG 1681-8)	Administrative Building (AD) - Teachers' Lounge in Admn Office	27	NO	N/A	N/A	5.5	3	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-M1-RM-HHW-FD (BLDG 1681-9)	Media Center (M) - Sink in Media Center	2.5	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A14-BATH-BOYS-HHWA-FD (BLDG 1681-17)	A-Wing - Boys' Bathroom in A-Wing	11	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A14-BATH-BOYS-HHWA-FD (BLDG 1681-18)	A-Wing - Boys' Bathroom in A-Wing	3.8	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A14-BATH-BOYS-HHWC-FD (BLDG 1681-19)	A-Wing - Boys' Bathroom in A-Wing	3.6	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A14-BATH-BOYS-HHWD-FD (BLDG 1681-20)	A-Wing - Boys' Bathroom in A-Wing	48	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A15-BATH-GIRLS-HHWA-FD (BLDG 1681-21)	A-Wing - Girls' Bathroom in A-Wing	35	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A15-BATH-GIRLS-HHWA-FD (BLDG 1681-22)	A-Wing - Girls' Bathroom in A-Wing	93	YES	N/A	N/A	1.5	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A15-BATH-GIRLS-HHWC-FD (BLDG 1681-23)	A-Wing - Girls' Bathroom in A-Wing	8.4	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A15-BATH-GIRLS-HHWD-FD (BLDG 1681-24)	A-Wing - Girls' Bathroom in A-Wing	54	YES	N/A	N/A	3.6	non-detect	Routine Control Measures Only	N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-A1-RM-HWCOMB-FD (BLDG 1681-25)	A-Wing - Storage for Music Room	10	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A3-RM-HWCOMB-FD (BLDG 1681-27)	A-Wing - Music Room	9.6	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A5-RM-HWCOMB-FD (BLDG 1681-29)	A-Wing - IT Room	39	YES	N/A	N/A	1.7	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A7-RM-HWCOMB-FD (BLDG 1681-31)	A-Wing - PTO Room	13	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A9-RM-HWCOMB-FD (BLDG 1681-33)	A-Wing - Girl Scouts Room	56	YES	N/A	N/A	1.8	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A11-RM-HWCOMB-FD (BLDG 1681-35)	A-Wing - Boy Scouts Room	10	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-AWING-HOSE-FD (BLDG 1681-38)	A-Wing - Hose located at end of A Wing	9.2	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A12-RM-HWCOMB-FD (BLDG 1681-39)	A-Wing - Storage Room	26	YES	N/A	N/A	2.3	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A10-RM-HWCOMB-FD (BLDG 1681-41)	A-Wing - Supply Storage	13	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A8-RM-HWCOMB-FD (BLDG 1681-43)	A-Wing - Supply Storage	3.8	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-A6-RM-HWCOMB-FD (BLDG 1681-45)	A-Wing - Supply Storage	46	YES	N/A	N/A	1.9	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-A2-RM-HWCOMB-FD (BLDG 1681-47)	A-Wing - Science Storage	140	YES	N/A	N/A	5.2	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-B18-BATH-GIRLS-HHWA-FD (BLDG 1681-49)	B-Wing - Girls' Bathroom in B-Wing	2.5	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-B18-BATH-GIRLS-HHWB-FD (BLDG 1681-50)	B-Wing - Girls' Bathroom in B-Wing	6.2	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B18-BATH-GIRLS-HHWC-FD (BLDG 1681-51)	B-Wing - Girls' Bathroom in B-Wing	34	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-B18-BATH-GIRLS-HHWD-FD (BLDG 1681-52)	B-Wing - Girls' Bathroom in B-Wing	5.1	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B18-BATH-GIRLS-HHWE-FD (BLDG 1681-53)	B-Wing - Girls' Bathroom in B-Wing	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B19-BATH-BOYS-HHWA-FD (BLDG 1681-55)	B-Wing - Boys' Bathroom in B-Wing	5.9	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B19-BATH-BOYS-HHWB-FD (BLDG 1681-56)	B-Wing - Boys' Bathroom in B-Wing	1.9	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B19-BATH-BOYS-HHWC-FD (BLDG 1681-57)	B-Wing - Boys' Bathroom in B-Wing	6.9	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B19-BATH-BOYS-HHWD-FD (BLDG 1681-58)	B-Wing - Boys' Bathroom in B-Wing	13	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B19-BATH-BOYS-HHWE-FD (BLDG 1681-59)	B-Wing - Boys' Bathroom in B-Wing	5.1	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-BWING-HOSE BY B1-FD (BLDG 1681-61)	B-Wing - Hose attachment by entrance to B1	3.4	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B1-RM-HWCMB-FD (BLDG 1681-62)	B-Wing - Computer Room	1.8	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B3-RM-HWCMB-FD (BLDG 1681-64)	B-Wing - Printer Room	16	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B2-LOUNGE-HWCMB-FD (BLDG 1681-66)	B-Wing - Teachers' Lounge	11	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)		Recommended Level = 20ppb	
Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)							Description	First Draw (ppb) (See note 2)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-B4A-RM- HWCOMB-FD (BLDG 1681-68)	B-Wing - School Psychologist	1.8	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B4B-RM- HWCOMB-FD (BLDG 1681-70)	B-Wing - Speech Therapy	15	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B6-RM- HWCOMB-FD (BLDG 1681-72)	B-Wing - Foreign Language	18	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B8-RM- HWCOMB-FD (BLDG 1681-74)	B-Wing - Gifted Students	1.3	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B10-RM- HWCOMB-FD (BLDG 1681-76)	B-Wing - Unlabeled Room	14	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B12-RM- HWCOMB-FD (BLDG 1681-78)	B-Wing - Book Storage	10	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B14-RM- HWCOMB-FD (BLDG 1681-81)	Rooms B14 and B16 combined into one bigger room - Art Room	2.1	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-B16-RM- HWCOMB-FD (BLDG 1681-84)	Rooms B14 and B16 combined into one bigger room - Art Room	1.3	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-BWING-HOSE-FD (BLDG 1681-87)	B-Wing - Hose located at end of B Wing	5	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C2-RM-LHWA-FD (BLDG 1681-90)	C-Wing - 2nd Grade Room	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C2-RM-LHWB-FD (BLDG 1681-91)	C-Wing - 2nd Grade Room	61	YES	N/A	N/A	8.7	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C4-RM- HWCOMB-FD (BLDG 1681-92)	C-Wing - 4th Grade Room	180	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C4-RM-LHWA-FD (BLDG 1681-94)	C-Wing - 4th Grade Room	190	YES	N/A	N/A	7.5	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C4-RM-LHWB-FD (BLDG 1681-95)	C-Wing - 4th Grade Room	200	YES	N/A	N/A	3.9	non-detect	Routine Control Measures Only	N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-C6-RM-HWCOMB-FD (BLDG 1681-96)	Rooms C6 and C8 combined into one bigger room - 3rd Grade Room	13	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C6-RM-LHW-FD (BLDG 1681-98)	Rooms C6 and C8 combined into one bigger room - 3rd Grade Room	7.9	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C8-RM-HWCOMB-FD (BLDG 1681-99)	Rooms C6 and C8 combined into one bigger room - 3rd Grade Room	40	YES	N/A	N/A	2.4	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C8-RM-LHW-FD (BLDG 1681-101)	Rooms C6 and C8 combined into one bigger room - 3rd Grade Room	29	YES	N/A	N/A	2.5	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C10-RM-HWCOMB-FD (BLDG 1681-102)	Rooms C10 and C12 combined into one bigger room - Kindergarten Room	15	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C10-RM-LHW-FD (BLDG 1681-104)	Rooms C10 and C12 combined into one bigger room - Kindergarten Room	97	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C12-RM-HWCOMB-FD (BLDG 1681-105)	Rooms C10 and C12 combined into one bigger room - Kindergarten Room	37	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C12-RM-LHW-FD (BLDG 1681-107)	Rooms C10 and C12 combined into one bigger room - Kindergarten Room	8.8	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C14-RM-HWCOMB-FD (BLDG 1681-108)	Rooms C14 and C16 combined into one bigger room - Pre-K (Sure Start) Room	11	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C14-RM-LHW-FD (BLDG 1681-110)	Rooms C14 and C16 combined into one bigger room - Pre-K (Sure Start) Room	16	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C16-RM-HWCOMB-FD (BLDG 1681-111)	Rooms C14 and C16 combined into one bigger room - Pre-K (Sure Start) Room	7.8	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-C16-RM-LHW-FD (BLDG 1681-113)	Rooms C14 and C16 combined into one bigger room - Pre-K (Sure Start) Room	36	YES	N/A	N/A	non-detect	7.9	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C15-RM-HWCOMB-FD (BLDG 1681-115)	Rooms C15 and C17 combined into one bigger room - PSCD Room	5	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C15-RM-LHW-FD (BLDG 1681-117)	Rooms C15 and C17 combined into one bigger room - PSCD Room	150	YES	N/A	N/A	2.8	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C17-RM-HWCOMB-FD (BLDG 1681-118)	Rooms C15 and C17 combined into one bigger room - PSCD Room	2.7	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C17-RM-LHW-FD (BLDG 1681-120)	Rooms C15 and C17 combined into one bigger room - PSCD Room	5.6	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C13-RM-HWCOMB-FD (BLDG 1681-121)	Rooms C11 and C13 combined into one bigger room - 4th Grade Room	530	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C13-RM-LHW-FD (BLDG 1681-123)	Rooms C11 and C13 combined into one bigger room - 4th Grade Room	7.4	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C11-RM-HWCOMB-FD (BLDG 1681-124)	Rooms C11 and C13 combined into one bigger room - 4th Grade Room	4	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C11-RM-LHW-FD (BLDG 1681-126)	Rooms C11 and C13 combined into one bigger room - 4th Grade Room	1500	YES	N/A	N/A	6	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C9-RM-HWCOMB-FD (BLDG 1681-127)	Rooms C9 and C7 combined into one bigger room - 1st Grade	46	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
First Draw (ppb)	Retest required?	Date Fixture Secured? (See Note 1)				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb) (See note 2)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			12/6/2014 through 1/10/2015			mm/dd/yyyy	1/10/2015 through 1/12/2015	1/10/2015 through 1/12/2016		mm/dd/yyyy	
RESULTS DATE			12/18/2014 through 1/18/2015			mm/dd/yyyy	1/13/2015 through 1/14/2015	1/13/2015 through 1/14/2016		mm/dd/yyyy	
WASHING	GTMO-1681-C9-RM-LHW-FD (BLDG 1681-129)	Rooms C9 and C7 combined into one bigger room - 1st Grade	46	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C7-RM-HWCOMB-FD (BLDG 1681-130)	Rooms C9 and C7 combined into one bigger room - 1st Grade	12	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C7-RM-LHW-FD (BLDG 1681-132)	Rooms C9 and C7 combined into one bigger room - 1st Grade	350	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C5-RM-HWCOMB-FD (BLDG 1681-133)	C-Wing - Unlabeled Room	11	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C5-RM-LHWA-FD (BLDG 1681-135)	C-Wing - Unlabeled Room	11	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-C5-RM-LHWB-FD (BLDG 1681-136)	C-Wing - Unlabeled Room	25	YES	N/A	N/A	non-detect	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C3-RM-HWCOMB-FD (BLDG 1681-137)	C-Wing - ET Room	1500	YES	N/A	N/A	9.3	non-detect	Routine Control Measures Only	N/A	N/A
WASHING	GTMO-1681-C1-RM-HWCOMB-FD (BLDG 1681-139)	C-Wing - Supply Room	7.3	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GTMO-1681-NURSE-HHW-FD (BLDG 1681-141)	Nurse's Office - Wash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A

Notes:
¹ Affected outlets were immediately secured after receiving verbal communication from the lab on results exceeding the recommended level of 20ppb.
² Post-remediation sampling not required since corrective action result was to take outlet out of service.
 after initial sampling and was resampled during follow sampling in JAN 2015.

*Outlet was replaced

Priority Areas Lead Testing and Corrective Actions December 2014 through January 2015
NS Guantanamo Bay ELEMENTARY SCHOOL BLDG 1681

Table 2. Summary Statistics

CATEGORY	INITIAL SAMPLING RESULTS	RE-SAMPLING RESULTS			POST REMEDIATION RESULTS
	Recommended Level = 20ppb				
	First Draw (ppb)	Water Fountain Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb)
Total Drinking	58	0	34	34	0
Total Drinking > 20 ppb	44	0	21	8	0
Total Cook/Brush	5	0	0	0	0
Total Cook/Brush > 20 ppb	0	0	0	0	0
Total Washing	83	0	28	28	0
Total Washing > 20 ppb	28	0	0	0	0
Total Samples	146	0	62	62	0
Total Samples > 20 ppb	72	0	21	8	0